



REFERENCE DRAWING	GSA-FL-SUM-055.500.RC	GSA-FL-SUM-089.500.RC
-------------------	-----------------------	-----------------------

ENVIRONMENTAL SURVEY DATA	22023+00	22028+00	22033+00	22038+00	22043+00	22048+00	22053+00	22058+00	22063+00	22068+00	22073+00	22076+00
---------------------------	----------	----------	----------	----------	----------	----------	----------	----------	----------	----------	----------	----------

SENSITIVE AREAS	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18	6a, 6b, 8, 16, 18
-----------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------	-------------------



HYDROSTATIC TEST SECTION		REFERENCE DRAWINGS		REVISIONS			MATERIALS		ENGINEERING APPROVALS				SABAL TRAIL PROJECT PROPOSED 36" PIPELINE STA. 22023+00 TO STA. 22076+00 ALIGNMENT SHEET		Sabal Trail TRANSMISSION					
DWG. NO.	DESCRIPTION	REV	DRN	DATE	DESCRIPTION	ITEM NO.	DESCRIPTION	QTY	TITLE	SIGNATURE	DATE	SIGNATURE	DATE	LOC.	YEAR	SHEET	SCALE	DWG.	REV.	
		0		06/29/2015	ISSUED FOR BID	1	36" O.D. x 0.520" W.T., API 5L X70, FBE 16 MILS w/I.D. EPOXY 1.7 MILS	3403 LF						SUMTER COUNTY, FLORIDA	2017	424 OF 492	1" = 200'	1657-PL-DG-70197-424	1	
		1		03/14/2016	ISSUED FOR CONSTRUCTION	3	36" O.D. x 0.750" W.T., API 5L X70, FBE 16 MILS w/I.D. EPOXY 1.7 MILS	1578 LF												
						4	36" O.D. x 0.750" W.T., API 5L X70, FBE 16 MILS, ARO 24 MILS, w/I.D. EPOXY 1.7 MILS	319 LF												
							GPW	GEOTEXTILE PIPE WEIGHT, 9000 LBS	83 EA											

Document Path: H:\GSA\1657\Deliverables\Alignment\Sheets\1657-PL-DG-70197-424.mxd
 GSA-FL-SUM-055.500.RC