

Whitewater Road Lift Station/Manhole Emergency Repair

Lowndes County has a collapsed manhole near the Whitewater lift station. The County desires to have the manhole replaced. The County feels this can best be accomplished by adding three new manholes, removing three manholes, and redirecting the flow. The attached map and table below shows the general description of the work to be accomplished. See below dates and times for mandatory meeting and proposal submission. Lowndes County specifications will govern this project except otherwise noted below.

JWA

- All manholes will be Raven lined
- All manhole lids will be composite
- All 8" pipe will be SDR 26

Prior to project bidding, the Contractor shall clarify with the Owner any discrepancy that exists between the requirements of the contract documents, drawings, and/or project specifications, regardless of any language in the contract documents, drawings, and/or project specifications that suggests one supersedes the other(s).

Item	Qty.		Description	Total
1	40+/-	LF	18" SDR 26 Sewer main	\$ 20,000.00
2	120+/-	LF	8" SDR 26 Sewer main	\$ 30,000.00
3	60+/-	LF	24" SDR 26 Sewer main	\$ 30,000.00
4	2	EA	5' Concrete manhole composite lid Raven lined	\$ 28,000.00
5	1	EA	6' Concrete manhole composite lid Raven lined	\$ 17,500.00
6	2	Lot	Core existing manhole & wet well	\$ 7,000.00
7	1	Lot	Tie in existing piping	\$ 1,500.00
8	1	EA	Install 6" SS vent pipe & charcoal filter on discharge MH 8' high	\$ 10,000.00
9	1	EA	Replace existing DC manhole ring and lid with composite lid	\$ 3,500.00
10	3	EA	Remove from premises obsolete manholes	\$ 5,000.00
11		Lot	Plug all obsolete lines on each end	\$ 2,000.00
12	1	EA	Labor to assist County with removal of sediment from wet well	\$ 500.00
13	1	EA	Replace one 12" stand pipe in wet well with 12" SDR 26 HDPE pipe	\$ 6,500.00
14	1	Lot	Bypass Pumping	\$ 15,000.00
			Total for all items above including installation, etc.	\$ 176,500.00
15	1	Lot	Sheet piling if required	\$ 30,000.00
16	1	Lot	Electrical relocation if required	\$ 5,000.00
17	1	Lot	Concrete removal from old lift station if required	\$ 3,500.00
18	1	Lot	Well pointing if required	\$ 12,000.00

Date contractor can mobilize Emergency bypass on or before 8/12 with materials to arrive starting 8/16, with work to begin once all materials are onsite.

- 8/6/2021 10:00am Mandatory Pre-bid Utilities office.
- 8/9/2021 [9:00am Questions due sstalvey@lowndescounty.com](mailto:sstalvey@lowndescounty.com)
- 8/9/2021 5:00pm Answers to questions returned.
- 8/10/2021 [12:00 Noon proposals due in Utilities office or sstalvey@lowndescounty.com](mailto:sstalvey@lowndescounty.com)