

WOODROW SAPP

WELL DRILLING, INC.

Serving Georgia, Florida, Alabama, and the Carolinas



Residential – Commercial
Industrial – Municipal
Water Systems

4774 NEW JESUP HIGHWAY
BRUNSWICK, GEORGIA 31520
Tel: 912 / 265-2603
FAX: 912 / 262-0423

May 10, 2023

Mr. Steve Stalvey
Director of Utilities
327 N. Ashley – 1st Floor
Valdosta, GA 31601

PROPOSAL TO INSTALL NEW PUMP ASSEMBLY AT STONE CREEK WELL

Woodrow Sapp Well Drilling is pleased to offer the following quotation for replacement of the line shaft/column assemblies and pump bowl assembly for the 18” Stone Creek well. The following components and services will be provided:

- New 8 Stage American Marsh 9HC 525GPM @ 342TDH
- 240ft x 6” x .280W Column Pipe w/ 1 -1/4” 416SS line shaft, couplings, bearing retainers with R3 inserts
- New motor shaft w/ adj. nut and key
- Packing box rebuild w/ new bearing and packing
- New cone strainer for bowl assembly
- Sandblast and paint existing discharge head assembly
- Install pump assembly and disinfect (includes crew, equipment, freight, and subsistence)
- Grout and seal discharge head

Total Price: \$64,095.00

Sincerely,

Henry “Bud” Rowe

**WOODROW SAPP
WELL DRILLING, INC.**