

ENG 2024-01: 2024 Resurfacing  
Project Information Sheet

**\*\*\* Pebble Creek Estates \*\*\***

**Fiddlers Bend Drive – .07 Miles – 23’ wide – Beginning at CR 897 (Pebble Creek Dr) Ending at CR 899 (Sandy Run Dr)**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping
- 2 Stop Bars (24” Thermoplastic)
- RPMs

**Pebble Creek Drive – .79 Miles – 23’ wide – Beginning at CR 777 (Cat Creek Rd) Ending at CR 897 (Pebble Creek Dr)**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping
- 2 Stop Bars (24” Thermoplastic)
- RPMs

**Sandy Run Drive – 0.28 Miles – 23’ wide – Beginning at CR 777 (Cat Creek Road) Ending at Dead End**

- Bituminous tack coat before each lift
- Leveling – 80lbs OGI
- Topping – 165lbs 12.5 mm Superpave
- Pick up all shoulder clippings on entire road
- Shoulder grading – see detail
- Permanent grassing (Hydro-seed)
- Temporary centerline stripe 4” wide – once after leveling
- Temporary centerline stripe 4” wide – once after topping
- Permanent centerline stripe 5” wide – 15 days after topping
- 1 Stop Bar (24” Thermoplastic)